

Subdivisional Lines, T. 2 S., R.31 E., W.M.

Chains		Feet
	E. on a random line bet. Secs. 28 & 33.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.90	Intersect N. & S. line, 60 lks. S. of Cor. to Secs. 27, 28, 33 & 34, from which Cor., I run	
	S.89° 34' W. on true line bet. Secs. 28 & 33. Descend hill.	
17.50	Foot of hill. Brook, 6 lks. wide, runs N. Ascend hill.	700
40.45	Set stone, 15 x 12 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.95	The Cor. to Secs. 28, 29, 32 & 33.	600
	Land; very hilly, steep and stony. Soil; 3rd rate.	
<hr/>		
	N. bet. Secs. 28 & 29.	
	Descend hill. Var. 20° E.	
40.00	Set stone, 16 x 12 x 6 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set a round stone, 16 x 10 in diameter for Cor. to Secs. 20, 21, 28 & 29.	400
	Land; rolling. Soil; good 2nd rate.	
<hr/>		
	E. on random line bet. Secs. 21 & 28.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.46	Intersect N. & S. line, 36 lks. S. of Cor. to Secs. 21, 22, 27 & 28, from which Cor., I run	
	S.89° 45' W. on true line bet. Secs. 21 & 28. Descend hill.	
27.50	Brook, 3 lks. wide, runs N. Foot of hill. Ascend.	
40.23	Set stone, 24 x 6 x 6, for $\frac{1}{4}$ Sec. Cor.	
60.00	Top of hill, brs. N. & S. Descend.	
80.46	The Cor. to Secs. 20, 21, 28 & 29.	
	Land; rolling. Soil; 2nd rate.	
	Nov. 20, 1864.	
<hr/>		
	N. bet. Secs. 20 & 21.	
	Descend hill. Var. 19 $\frac{1}{2}$ ° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 16, 17, 20 & 21, in mound of earth, with charred stake, pits, etc., as per instructions.	200
	Land; gently rolling. Soil; 1st rate.	