

Subdivisional Lines, T. 2 S., R. 31 E., W.M.

Chains		Feet
	E. on a random line bet. Secs. 16 & 21.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect N. & S. line, 28 lks. S. of Cor. to Secs. 15, 16, 21 & 22, from which Cor., I run	
	S. $89^{\circ} 48'$ W. on true line bet. Secs. 16 & 21. Descend hill.	
9.00	Foot of hill. Brook, 5 lks. wide runs N.E. Ascend.	50
40.20	Set stone, 20 x 6 x 6 for $\frac{1}{4}$ Sec. Cor.	
45.00	Top of hill brs. N. & S. Descend.	250
80.40	The Cor. to Secs. 16, 17, 20 & 21.	150
	Land; rolling. Soil; 1st rate.	
<hr/>		
	N. bet. Secs. 16 & 17.	
	Descend hill. Var. $19\frac{1}{2}^{\circ}$ E.	
22.62	Foot of hill. Brook, 5 lks. wide, runs N.E. Ascend hill.	
40.00	Set stone, 18 x 12 x 8, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone for Cor. to Secs. 8, 9, 16 & 17.	
	Land; rolling. Soil; good 2nd rate.	
<hr/>		
	E. on random line bet. Secs. 9 & 16.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersect N. & S. line at Cor. to Secs. 9, 10, 15 & 16, from which, I run	
	W. on true line bet. Secs. 9 & 16. Ascend hill.	
40.10	Set stone, 18 x 10 x 10 for $\frac{1}{4}$ Sec. Cor. Top of hill brs. N.	500
80.20	and S., descend.	
80.20	The Cor. to Secs. 8, 9, 16 & 17.	500
	Land; hilly. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 8 & 9.	
	Ascend hill. Var. $19\frac{1}{2}^{\circ}$ E.	
35.00	Top of hill brs. N.E. & S.W.	50
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 4, 5, 8 & 9, in mound of earth, with charred stake, pits, etc., as per instructions.	
	Land; gently rolling. Soil; 1st rate.	