

Subdivisional Lines, T. 2 S., R. 31 E., W.M.

Chains		Feet
	N. bet. Secs. 17 & 18. Ascend hill. Var. 20° E.	
40.00	Set stone, 18 x 9 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 17 x 10 x 10, for Cor. to Secs. 7, 8, 17 & 18. Land; gently rolling. Soil; good 2nd rate.	+250
	E. on random line bet. Secs. 8 & 17.	
40.00	Set post for Temp. Cor. Sec. Cor.	
80.50	Intersect N. & S. line at Cor. to Secs. 8, 9, 16 & 17, from which, I run W. over true line bet. Secs. 8 & 17. Ascend hill.	
30.00	Top of hill brs. N. & S.	
40.25	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
70.00	Deep ravine brs. N. 80° E.	
80.50	The Cor. to Secs. 7, 8, 17 & 18. Land; rough and broken. Soil; 2nd rate.	
	W. on random line bet. Secs. 7 & 18.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect W. Bdy., 21 lks. S. of Cor. to Secs. 7 & 18, from which, I run S. 89° 51' E. on true line bet. Secs. 7 & 18.	
40.50	Set stone, 15 x 10 x 5 for $\frac{1}{4}$ Secs. Cor.	
64.00	Ravine brs. N.E.	
80.50	The Cor. to Secs. 7, 8, 17 & 18. Land; rolling. Soil; good 2nd rate.	
	N. bet. Secs. 7 & 8. Var. 18 $\frac{1}{2}$ ° E.	
21.00	Ravine brs. N.E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set stone, 18 x 10 x 8 for Cor. to Secs. 5, 6, 7 & 8. Land; rolling. Soil; 1st rate.	