

Subdivisional Lines, T. 2 S., R. 31 E., W.M.

Chains		Feet
	E. on random line bet. Secs. 5 & 8.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.28	Intersect N. & S. line, 10 lks. N. of Cor. to Secs. 4, 5, 8 & 9, from which Cor., I run N. 89° 56' W. on true line bet. Secs. 5 & 8.	
40.14	Set stone, 18 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	
80.28	The Cor. to Secs. 5, 6, 7 & 8. Land; level. Soil; 1st rate.	
<hr/>		
	W. on random line bet. Secs. 6 & 7.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.60	Intersect W. Bdy., 45 lks. N. of Cor. to Secs. 6 & 7, from which, I run N. 89° 41' E. on true line bet. Secs. 6 & 7.	
40.60	Set stone, 30 x 24 x 18, for $\frac{1}{4}$ Sec. Cor.	
80.60	The Cor. to Secs. 5, 6, 7, & 8. Land; level. Soil; 1st rate.	
<hr/>		
	N. on random line bet. Secs. 5 & 6. Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.34	Intersect N. Bdy., 51 lks. E. of Cor. to Secs. 5 & 6, from which, I run S. 0° 22' E. on true line bet. Secs. 5 & 6, ascend hill.	
39.34	Set stone, 20 x 10 x 10, for $\frac{1}{4}$ Sec. Cor.	
79.34	The Cor. to Secs. 5, 6, 7, & 8. Land; gently rolling. Soil; 1st rate. Nov. 22, 1864.	
<hr/>		
General Description.		
<hr/>		
This Tp. is generally high and rolling, covered with excellent grass and is well watered with numerous streams and spring branches, where they are united forming Birch Creek.		
There is but a small amount of agricultural land and what		