

Exterior Bdys. Tp. 2 S., R.32 E., W.M.
 As surveyed by David P. Thompson, U.S. Deputy Surveyor,
 Under Contract No. 106,
 Dated Aug. 16, 1864.

Chains		Feet
	I begin at the Cor. to Tps. 2 & 3 S., Rs. 31 & 32 E. and run	
	E. on S. Bdy. of Sec. 31	
	Var. 19° E.	
	Descend hill.	
22.50	Creek, 6 lks. wide runs N.W.. Foot of hill. Ascend hill.	700
38.50	Spring flows S.	
40.00	Set stone, 20 x 15 x 10 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 24 x 10 x 10 ins. for Cor. to Secs. 31, 32, 5 and 6.	600
	Land; very steep and stony. Soil; 3rd rate.	
	E. on S. Bdy. of Secs. 32.	
	Var. 24° E.	
	Ascend hill.	
37.00	Ravine, course S.W.	
40.00	Set stone, 15 x 8 x 6 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 20 x 12 x 10 ins. for Cor. to Secs. 32, 33, 4 and 5.	
	Enter timber, brs. N. & S.	
	Land; hilly. Soil; 2nd rate.	
	E. on S. Bdy. of Sec. 33.	
	Var. 21° E.	
	Ascend hill.	
40.00	Set stone, 15 x 12 x 4 ins., for $\frac{1}{4}$ Sec. Cor.	
74.00	Brook, 3 lks. wide, runs N.	
80.00	Set stone, 16 x 12 x 5 ins., for Cor. to Secs. 3, 4, 33 & 34.	400
	Land; hilly. Soil; 2nd rate. Timber; fir, pine & larch.	
	E. on S. Bdy. of Secs. 34	
	Var. 20° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., from which, A fir, 8 ins. diam., brs. N.40° W., 13 lks. dist. A " 12 " " " S. 5° W., 5 " "	