

Exterior Bdays. T.3 S., R.32 E., W.M.

Chains		Feet
64.50	A ravine, course N.W.	
80.00	To a point, 96 lks. N. of old Cor., which is a stone, marked with 4 notches on E. edge. Ascent about 200 ft. Set stone, basalt, 18 x 14 x 4 ins., in a mound of stone, on S. slope, near top of hill, for Cor. to Secs. 32 & 33, marked with 2 notches on W. and 4 notches on E. edges. Land; surface very rolling. Soil; 2nd & 3rd rate. Good grass.	
E. on S. Bdy. of Sec. 33.		
Var. 22° 00' E.		
27.00	A brook, 4 lks. wide and ravine, course N.W. Descent 100 ft.	
40.00	No trace of old Cor. Set a basalt stone, 20 x 14 x 7 ins., in mound of stone, on S.W. slope, near top of hill, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ and X on N. face.	
46.00	Top of ridge and enter timber, course N. & S. Ascent 100 ft.	
75.75	A brook, 4 lks. wide, course N.W. Descent 200 ft.	
80.00	Set basalt stone, 18 x 8 x 6 ins., 12 ins. in ground, on S.W. slope, for Cor. to Secs. 33 & 34, marked with 3 notches on E. and W. edges. A pine, 36 ins. diam., brs. N.28° E., 102 lks. dist., marked T.2 S., R.32 E., S.34, B.T. A pine, 16 ins. diam., brs. N.22° W., 70 lks. dist., marked T.2 S., R.32 E., S.33, B.T. Trees marked on S. side would be all wrong, so I do not mark any. Land; surface very rolling. Soil; 3rd & 2nd rate. Scattering timber in places near streams; pine, tamarack and fir.	+ 50
E. on S. Bdy. of Sec. 34.		
Var. 21° 45' E.		
Ascending.		
24.50	Top of ridge, course N. & S. about 300 ft. above Sec. Cor.	
34.00	Enter timber, course N. & S.	
40.00	No trace of old Cor.	