

Subdivisional Lines, T. 2 S., R.32 E., W.M.

Chains	Feet
earth, with charred stake, pits, etc., as per instructions.	
Land; hilly. Soil; 2nd rate.	
<hr/>	
E. on random line bet. Secs. 12 & 13.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.67	Intersect E. Bdy. at post Cor. to Secs. 12 & 13, from which I run
W. on true line bet. Secs. 12 & 13.	
15.50	Brook, 2 lks. wide, runs N. Ascend.
39.84	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.
79.67	The Cor. to Secs. 11, 12, 13 & 14. +150
Land; rolling. Soil; 2nd rate.	
<hr/>	
N. bet. Secs. 11 & 12.	
Descend hill. Var. 20° E.	
17.25	Birch Creek, 12 lks. wide, runs W. Foot of hill. Ascend hill. -200
18.00	Road brs. E. & W.
40.00	Set stone, 14 x 8 x 8 for $\frac{1}{4}$ Sec. Cor.
80.00	Set stone, 18 x 8 x 6, for Cor. to Secs. 1, 2, 11 & 12. +1000
Land; hilly. Soil; 2nd rate.	
Nov. 23, 1864.	
<hr/>	
E. on random line bet. Secs. 1 & 12..	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.81	Intersect E. Bdy. at Cor. to Secs. 1 & 12, from which Cor., I run
W. on true line bet. Secs. 1 & 12. Ascend hill. +300	
30.00	Top of hill brs. N.E. & S.W. Descend.
39.90	Set stone, 15 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.
79.81	The Cor. to Secs. 1, 2, 11, & 12. -150
Land; hilly. Soil; 2nd rate. Good grass.	
<hr/>	
N. on random line bet. Secs. 1 & 2..	
Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.