

## Subdivisional Lines, T. 2 S., R. 32 E., W.M.

Chains		Feet
	W. on a true line bet. Secs. 29 & 30. Descend hill.	
36.00	Foot of hill. Brook, 6 lks. wide, runs N. Ascend hill	500
40.00	Set stone, 24 x 10 x 6, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 30 x 20 x 12, for Cor. to Secs. 29, 30, 31 & 32. Land; very rough and stony. Soil; 3rd rate.	1000
N. bet. Secs. 29 & 30.		
	Descend hill. Var. 21° E.	
40.00	Set stone, 15 x 12 x 6, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 26 x 15 x 6, for Cor. to Secs. 19, 20, 29 & 30. Land; hilly. Soil; 2nd rate.	700
E. on random line bet. Secs. 20 & 29.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.76	Intersect N. & S. line, 54 lks. N. of Cor. to Secs. 20, 21, 28 & 29, from which, I run	
	N. 89° 37' W. on true line bet. Secs. 20 & 29. Descend hill.	
21.00	Foot of hill. Brook, 5 lks. wide, runs N.E. ascend hill.	400
40.38	Set stone, 16 x 12 x 10, for $\frac{1}{4}$ Sec. Cor.	
80.76	The Cor. to Secs. 19, 20, 29 & 30. Land; hilly. Soil; 2nd rate.	500
N. bet. Secs. 19 & 20.		
	Var. 22° E.	
40.00	Set stone, 26 x 10 x 10, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 17, 18, 19 & 20, in mound of earth, with charred stake, pits, etc. as per instructions.	
	Land; steep and stony. Soil; 3rd rate.	600
E. on random line bet. Secs. 17 & 20.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.54	Intersect N. & S. line, 36 lks. N. of Cor. to Secs. 16, 17, 20 & 21, from which, I run	
	N. 89° 45' W. on true line bet. Secs. 17 & 20.	
40.27	Set stone, 16 x 12 x 10, for $\frac{1}{4}$ Sec. Cor.	