

Subdivisional Lines, T.2 S., R.32 E., W. M.

Chains		Feet
	which, I run	
	N.89° 53' E. on true line bet. Secs. 7 & 18. Descend hill.	
38.50	Foot of hill. Ascend.	
40.26	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
70.00	Top of hill brs. N. & S. Descend.	
80.26	The Cor. to Secs. 7, 8, 17 & 18. Land; hilly. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 7 & 8.	
	Var. 18 $\frac{1}{2}$ °E.	
	Descend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
72.20	Ravine brs. N. W. & S. E.	
80.00	Set stone, 18 x 8 x 8, for Cor. to Secs. 5, 6, 7 & 8. Land; hilly, sloping N. Soil; 2nd rate.	-500
<hr/>		
	E. on random line bet. Secs. 5 & 8.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.10	Intersect N. & S. line at Cor. to Secs. 4, 5, 8 & 9, from which, I run	
	W. on true line bet. Secs. 5 & 8. Descend hill	
20.00	Foot of hill.	
40.05	Set stone, 14 x 6 x 8 for $\frac{1}{4}$ Sec. Cor. Ascend hill.	
80.00	The Cor. to Secs. 5, 6, 7 & 8. Land; rolling. Soil; 2nd rate.	
<hr/>		
	W. on random line bet. Secs. 6 & 7.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.16	Intersect W. Bdy., 17 lks. N. of Cor. to Secs. 6 & 7, from which, I run	
	N.89° 53' E. on true line bet. Secs. 6 & 7. Descend hill.	
40.16	Set stone, 18 x 8 x 8 for $\frac{1}{4}$ Sec. Cor.	-500
77.50	Ravine brs. N.W. & S.E. Ascend.	