

## Subdivisional Lines, T. 2 S., R. 32 E., W.M.

Chains		Feet
	<p>1½ ft. high x 3½ ft. base over Cor., from which,</p> <p>A pine, 14 ins. diam., brs. N.85° W., 53 lks. dist., marked T.2 S., R.32 E., S.27, B.T.</p> <p>A pine, 38 ins. diam., brs. S.1° E., 135 lks. dist., marked T.2 S., R.32 E., S. 35, B.T.</p> <p>No other tree in limits.</p> <p>Land; mountainous, 80.00 chs.</p> <p>Soil; stony, 5th rate.</p> <p>Timber; open pine, fir &amp; tamarack, 26.00 chs.</p>	
	<p>E. on random line bet. Secs. 26 &amp; 35.</p> <p>Var. 20° 00' E.</p>	
40.00	Set temp. ¼ Sec. Cor.	
79.35	Intersect N. & S. line, 59 lks. S. of Cor. to Secs. 25, 26, 35 & 36.	
	Thence I run Descend.	
	S. 89° 35' W. on true line bet. Secs. 26 & 35.	
	Var. 22° 00' E.	
	Descend.	
7.35	Ravine, course N. Ascend 5°	175
12.35	Top of mountain. Descend 5°	1200
39.68	Set basalt stone, 18 x 12 x 6 ins., 8 ins. in ground, for ¼ Sec. Cor. (digging impracticable), marked ¼ on N. face, and raised mound of stone, 1½ ft. high x 3½ ft. base over Cor., 160 lks. W. of ledge of basalt rock. Pits impracticable.	
49.35	Enter timber.	
52.05	Ogilvey Creek, 38 lks. wide, N.15° E. Ascend 25°	
71.35	Summit of ridge falls N.35° E. Descend 15°	100
74.85	Ravine, course N.E. Ascend 15°	150
79.35	The Cor. to Secs. 26, 27, 34 & 35.	
	Land; mountainous, 79.35 chs.	
	Soil; stony, 5th rate.	
	Timber; pine, fir and tamarack, 30.00 chs.	
	Undergrowth; same as timber, 12.00 chs.	