

## Subdivisional Lines, T. 2 S., R. 32 E., W. M.

Chains		Feet
	No other tree in limits.	
65.60	Saw Mill Creek, 6 lks. wide, runs W. Ascend 30°.	
73.35	Leave timber.	
79.35	The Cor. to Secs. 27, 28, 33 & 34. Land; mountainous, 79.35 chs. Soil; stony, 4th rate. Timber; pine, fir and tamarack, 73.35 chs. Undergrowth of same timber, 20.00 chs. Good grass. Oct. 2, 1891.	
W. bet. Secs. 28 & 33. Ascend Var. 20° 30' E.		
27.00	Summit falls S.W. Descend 20°	900
40.00	Set basalt stone, 16 x 12 x 6 ins., 8 ins. in ground, (digging imprac.) for $\frac{1}{2}$ Sec. Cor., marked $\frac{1}{2}$ on N. face, raised mound of stone, 2 ft. high x 4 ft. base over Cor. Pits impracticable. No traces of any other Cor. at this place.	
43.00	Ravine, course S.W. Ascend 10°	150
53.00	Summit of ridge falls S. 30° W. Descend 20°	100
80.00	Set basalt stone, 14 x 10 x 5 ins., 10 ins. in ground, for Cor. to Secs. 28, 29, 32 & 33, marked 4 notches on E. of edge and 1 notch on S. face; dug pits, 18 x 18 x 12 ins. in each Secs., 5 $\frac{1}{2}$ ft. dist. and raised mound of earth, 2 ft. high x 4 ft. base alongside, from which, A quaken aspen, 8 ins. diam., brs. N. 32° W., 250 lks. dist., marked T. 2 S., R. 32 E., S. 29, B. T. No other tree in limits. No traces of any other Cor. at this place. Land; mountainous, 80.00 chs. Soil; stony, 4th rate. Scattering pine, fir and quakenasp. No undergrowth. Good grass.	
S. on random line bet. Secs. 32 & 33. Var. 20° 40' E.		