

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W. M.

Chains	
	S. bet. Secs. 23 & 24.
	Var. 20°00'E.
	Ascend.
3.83	Summit.
	Descend.
17.00	Wagon road, brs. E. & W.
17.75	N. Fork of Birch Creek, 20 lks. wide, runs W.
	Enter timber.
	Ascend steep, stony mountain.
20.75	Leave timber.
25.75	Enter timber.
40.00	Set basalt stone, 18 x 18 x 6 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone 2 ft. high by 4 ft. base over Cor.; pits impracticable.
50.00	Leave timber.
	Descend.
52.00	Summit.
61.00	Spring, brs. W., 50 lks. dist.
80.00	A basalt stone, in place, 24 x 12 x 12 ins., above ground, for Cor. to Secs. 23, 24, 25 & 26, marked with 4 notches on N. and 2 notches on E. edges. A cross, (X), at exact point, in brushy ravine, course W., from which, A willow, 4 ins. diam., brs. S.70°E., 17 lks. dist., marked T2SR33ES25BT A willow, 3 $\frac{1}{2}$ ins. diam., brs. S.15°W., 17 lks. dist., marked T2SR33ES26BT. A willow, 3 ins. diam., brs. N.15°W., 10 lks. dist., marked T2SR33ES23BT. No other tree in limits. Made mound of stone, 1 $\frac{1}{2}$ ft. high by 3 $\frac{1}{2}$ ft. base, in Sec. 24, 5 $\frac{1}{2}$ ft. dist. Land; mountainous & stony, 80.00 chs. Timber; pine, fir & larch, 27.25 chs. Undergrowth; same as timber. Soil; 4th rate.