

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet.
80.05	<p>Intersect E. Bdy. of Tp., 62 lks. N. of Cor. to Secs. 25, 30, 31 &amp; 36, which is a basalt stone, 14 x 12 x 3 ins., in mound of stone, 1½ ft. high x 2½ ft. base, on gentle E. slope, and marked 5 notches on N. and 1 notch on S. face, from which,</p> <p>A pine, 18 ins. diam., brs. N.20°E., 132 lks. dist., marked T.2 S., R.34 E., S.30, B.T.</p> <p>A fir, 20 ins. diam., brs. S.52°E., 35 lks. dist., marked S.31, B.T.</p> <p>A pine, 20 ins. diam., brs. S.42° W., 62 lks. dist., marked R.33 E., S.36, B.T.</p> <p>A pine, 30 ins. diam., brs. N.85° W., 86 lks. dist., marked S.25, B.T.</p>	
	Thence I run	
		Var.23° 30' E.
	Ascend through timber.	
	N.89° 33' W. on true line bet. Secs. 25 & 36.	
5.05	Wagon road brs. N.E. & S.W.	
20.05	Leave timber.	
40.02	<p>Set basalt stone, 16 x 13 x 13 ins., marked ¼ on N. face. As digging at this point, is impracticable, I made a mound of stone, 4 ft. high x 5 ft. base over the Cor. stone, on summit of mountain. Descend.</p>	
45.05	Enter timber.	
76.05	Birch Creek, 15 lks. wide, runs N.	
80.05	The Cor. to Secs. 25, 26, 35 & 36.	
	Land; mountainous throughout this line, 80.05 chs.	
	Timber; pine, fir and larch, with dense undergrowth of same,	
	55.05 chs.	
	Soil; stony 4th rate. Good grass on N. slopes.	
		Sept. 23, 1890.
	S. on random line bet. Secs. 35 & 36.	
		Var.24°15'E.
	Ascend through brush and timber.	
40.00	Set temp. ¼ Sec. Cor.	