

Exterior & Subdivisional Lines, T. 2 S., R. 33 E., W.M.

Chains		Feet
	From Closing Cor. to Secs. 15 & 14, on Reservation Bdy., which is a basalt stone, 16 x 10 x 5 ins., marked URCC on N. face, and in mound of stone, 2 ft. high x 4 ft. base, on S.W. face of hill.	
	Thence I run	
		Var. 23°30' E.
	S. bet. Secs. 14 & 15. Descend from summit.	
17.50	Gulch, course S.W.	Ascend.
23.00	Summit of ridge falls W.	Descend.
30.50	Canyon, course W. Enter brush.	Ascend.
33.92	Set basalt stone, 14 x 10 x 6 ins., 10 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Dug pits, 18 x 18 x 12 ins., N. & S. of stone, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth, 2 ft. high x 4 ft. base over Cor., on N. hillside, from which, A fir, 8 ins. diam., brs. E. 100 lks. dist., marked $\frac{1}{4}$ S., B.T. No other tree in limits.	
37.75	Leave brush.	
39.00	Summit of ridge falls S.W.	Descend.
49.00	Head of ravine, course S.W.	Ascend.
61.00	Summit of ridge falls S.W. Descend steep, stony mountain side.	
73.92	Set basalt stone, 18 x 10 x 8 ins., 12 ins. in ground, for Cor. to Secs. 14, 15, 22 & 23, marked 3 notches on N. face and 2 notches on E. face. Raised mound of stone, 2 ft. high x 3 $\frac{1}{2}$ ft. base over Cor. on S. hillside. Pits impracticable. Land; mountainous, 73.92 chs. Scattering pine, fir & tamarack trees, with undergrowth of same, 7.25 chs. Soil; stony 5th rate. Some grass.	
	E. on random line bet. Secs. 14 & 23.	
		Var. 17°30' E.
	Ascend.	