

Exterior & Subdivisional Lines, T. 2 S., R.33 E., W.M.

| Chains | | Feet |
|--------|---|------|
| | line, 20 chs. over mountainous and stony land. Sept. 27th, 1890. | |
| | I commence at $\frac{1}{4}$ Sec. Cor., bet. Secs. 9 & 10, which is, also, a Closing Cor., for said Secs. on Reservation Bdy., and is a basalt stone, 14 x 10 x 8 ins., in stone mound, 1 ft. high x 2 ft. base, marked U.R.C.C. No other marks visible. Thence I run S. bet. Secs. 9 & 10. Var. 19° 45' E. | |
| 0.75 | Daly Wagon road N.E. & S.W. Descend. | |
| 33.15 | Canyon, course S.W. | -500 |
| 40.00 | Set basalt stone, 12 x 8 x 4 ins., 8 ins. in ground, for Cor. to Secs. 9, 10, 15 & 16, marked 4 notches on S. face and 3 notches on E. face; dug pits, 18 x 18 x 12 ins., in each Sec. Cor., 5 $\frac{1}{2}$ ft. dist. Raised mound of earth, 2 ft. high x 4 $\frac{1}{2}$ ft. base over Cor., on W. hill-side. Land; mountainous, 40 chs. Good grass. Soil; 4th rate. No timber. | |
| | E. on random line bet. Secs. 10 & 15. Var. 19° 45' E. | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 46.50 | Intersect Reservation Bdy., 40 lks. S. of Closing Cor. to Secs. 10 & 15, which is a basalt stone, 16 x 12 x 5 ins. in mound of stone, 1 $\frac{1}{2}$ ft. high x 3 ft. base, marked U.R.C.C. Thence I run S. 89° 30' W. on true line bet. Secs. 10 & 15. Ascend Var. 20° 00' E. | |
| 0.32 | Daly Wagon Road, N.W. & S.E. | |
| 1.50 | Summit of mountain, ridge brs. N.W. & S.E. | |
| 6.43 | Set basalt stone, 33 x 8 x 6 ins., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. Raised mound of stone, 1 $\frac{1}{2}$ ft. | |