

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	Var. 18°20' E.	
10.20	Set basalt stone, 12 x 7 x 6 ins., 8 ins. in ground, for Cor. to Secs. 4, 5, 8 & 9, marked 5 notches on S. and 4 notches on E. Raised mound of stone, 2 ft. high x 4½ ft. base over the stone, on S.W. hillside. Pits impracticable. Land; mountainous & stony, 10.20 chs. Soil; 5th rate. No timber.	
	E. on random line bet. Secs. 4 & 9.	
	Var. 18°45' E.	
4.83	Daly Wagon road, course N.W. & S.E.	
5.98	Intersect N. & S. line at Closing Cor. to Secs. 4 & 9 on Reservation Bdy., which is a basalt stone, 18 x 12 x 4 ins., in mound of stone, 1 ft. high x 2½ ft. base, marked U.R. on N. face, and C.C. on S. face, on E. hillside. Thence I run, Var. 18°45' E.	
	W. on true line bet. Secs. 4 & 9.	
1.15	Daly Wagon road brs. N.W. & S.E.	
5.98	The Cor. to Secs. 4, 5, 8 & 9. Land; mountainous & stony, 5.98 chs. No timber. Soil; 5th rate.	
	S. bet. Secs. 8 & 9. Descend.	
	Var. 18°45' E.	
8.50	Head of ravine, W. Ascend gently.	-300
12.50	Summit of ridge falls W. Descend.	
22.25	Deep canyon, course W. Ascend abruptly.	-400
35.50	Summit of ridge falls W. Descend.	
40.00	Set basalt stone, 18 x 8 x 6 ins., 12 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face. Raised mound of stone 2 ft. high x 3½ ft. base over Cor., on S.W. face of hill. Pits impracticable.	
51.25	Canyon, course S.W. Ascend.	-200
63.50	Summit of ridge falls S.W. Descend.	
80.00	Set basalt stone, 15 x 10 x 10 ins., 10 ins. in ground, for Cor. to Secs. 8, 9, 16 & 17, marked 4 notches on S., and	