

Exterior & Subdivisional Lines, T.2 S.; R.33E., W.M.

Chains		Feet
	<p>and 2 notches on W. face, G.C. on N. Raised mound of stone, 2 ft. high x 4 ft. base over Cor., from which, A fir, 10 ins. diam., brs. N. 65° W., about 100 lks. dist., marked T.2 S., R.33 E., S.32, B.T.</p> <p>No other tree in limits. Pits impracticable.</p> <p style="text-align: right;">Var. 18°00' E.</p> <p>Land; mountainous, 53.40 chs.</p> <p>Timber; pine, fir and tamarack, scattering along the whole line, with dense undergrowth of same, 9.00 chs.</p> <p>Soil; stony, 4th rate. Good grass.</p>	
	<p>I commence at Cor. to Secs. 5, 6, 31 & 32 on N. Bdy. of Tp., which is a basalt stone, 14 x 10 x 8 ins., 10 ins. in ground, marked 5 notches on E. and 1 notch on W., with mound of stone & earth, 2 ft. high x 4½ ft. base alongside alongside, on N. hillside.</p> <p>Thence I run,</p> <p>S. bet. Secs. 5 & 6.</p> <p style="text-align: right;">Var. 25°30' E.</p>	
9.85	<p>Intersect Reservation Bdy. at Closing Cor. to Secs. 5 & 6, which is a basalt stone, 16 x 12 x 10 ins., 8 ins. in ground, marked U.R.C.C. on W. face, and in a stone mound 1 ft. high x 2 ft. base.</p>	
13.25	Summit of ridge N.38°E.	Descend.
17.50	Daly Wagon road brs. N.38°E. & S.38° W.	
38.50	Gulch, course N.28°E.	Ascend.
40.00	<p>The ¼ Sec. Cor. bet. Secs. 5 & 6; a basalt stone, 10 x 8 x 7 ins., loose, in mound of stone, 1½ ft. high x 3 ft. base, and marked ¼ on W.</p>	
41.00	Gulch, course N.W.	Ascend.
71.10	Daly Wagon road brs. N.35° W. & S.35° E.	
71.50	<p>Intersect Reservation Bdy. N.80°W., 10 lks. dist. from mound of stone, 1½ ft. high x 3 ft. base, purporting to be Closing Cor. to Secs. 5 & 6. I find no stone marked.</p> <p>At point of intersection, I set a basalt stone, 18 x 12 x 4 ins., 12 ins. in ground, for Closing Cor. to Secs. 5 & 6.</p>	