

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	<p>Set basalt stone, 28 x 10 x 6 ins., 21 ins. in ground, at point of temp. Cor., for true Cor. to Secs. 1, 6, 7, & 12, marked 5 notches on S. and 1 notch on N. Raised mound of stone, 2 ft. high x 4½ ft. base over Cor., on E. hillside. Var. 25°30'E.</p> <p>At the point of intersection of line bet. Secs. 6 & 7, with W. Bdy. of Tp.,</p> <p>I set a basalt stone, 26 x 10 x 8 ins., 20 ins. in ground, for Closing Cor. to Secs. 6 & 7, marked 1 notch on N. & 5 notches on S. & C.G. on W.; dug pits, 18 x 18 x 12 ins. N., S. & E. of stone, 5½ ft. dist. Raised mound of stone and earth, 2 ft. high x 4½ ft. base over Cor., on E. hillside. Var. 19°15' E.</p> <p>No timber. Soil; stony 5th rate.</p> <p>The whole line passes over mountainous land.</p>	
	S. bet. Secs. 7 & 8.	<p>Descend 25°.</p> <p>Var. 19°45'E.</p>
9.75	Canyon, course S.W.	Ascend 15°
17.50	Summit of ridge falls S.W.	Descend 28°
34.00	Canyon, course S.60°W.	Ascend 15°
40.00	Set basalt stone, 14 x 10 x 8 ins., 10 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of Cor., 5½ ft. dist. Raised mound of earth, 1½ ft. high x 3 ft. base alongside, on hillside facing West.	
54.50	Summit of ridge, S.W. & N.E.	Descend 40°
80.00	Set basalt stone, 18 x 8 x 6 ins., 12 ins. in ground, for Cor. to Secs. 7, 8, 17 & 18, marked 4 notches on S., & 5 notches on E. face. Raised mound of stone, 1½ ft. high x 3½ ft. base over stone. Pits impracticable, on S. face of hill.	
	No timber. Soil; stony 4th rate.	
	Land; mountainous, 80.00 chs.	
	Sept. 22, 1891.	