

41.

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
64.00	Enter thick brush.	
64.75	Birch Creek, 15 lks. wide, course N.75°W.	
82.00	" " " " " " S.W.	
84.50	" " " " " " N.W.	
110.00	Leave brush. Ascend.	
132.00	Summit of ridge falls N.15°W.	+300
135.70	Intersect W. Bdy. of Tp., 506 lks. S. of Cor. to Secs. 7, 12, 13 & 18, which is a post, 4 x 4 ins., 24 ins. above ground, marks indistinct from age, at Cor. of fence N., S. & W. on N.W. hillside.	
	Var.20°00' E.	
	At point of intersection, I	
	Set basalt stone, 18 x 12 x 4 ins., 12 ins. in ground, for Closing Cor. to Secs. 7 & 18, marked 2 notches on N., 4 notches on S., & C.C. on W. face; dug pits, 18 x 18 x 12 ins., N., S. & E. of Cor., 5½ ft. dist. Raised mound of earth & stone, 1½ ft. high x 3½ ft. base over Cor. J.A.Horn's house brs. N.42°30' W. from this Cor., 285 lks. dist.	
	Land; rocky & mountainous for 75 chs.	
	Dense undergrowth, mostly cottonwood, 48 chs. The remainder of this line, 12.20 chs., comparatively level.	
	Soil; on creek bottom, good; elsewhere 4th rate.	
	S. bet. Secs. 17 & 18.	Descend 35° Var.17°12'E.
10.75	Wagon road, course E. & W.	
11.00	Enter meadow, fence E. & W. Foot of descent.	
13.00	Jas. Jordan's house brs. E.425 lks. dist.	
14.40	Birch Creek, 15 lks. wide, course W.	
16.50	Leave meadow, fence E. & W. Enter timber, Ascend 30°.	
35.00	" timber.	
40.00	Set basalt stone, 14 x 8 x 5 ins., 10 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of stone, 5½ ft. dist. Raised mound of stone 1½ ft. high x 3½ ft. base alongside, on N.W. hillside.	