

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	W. bet. Secs. 18 & 19. Var. 22°35'E.	
1.50	Ravine, S.70°W., Enter dense brush. Ascend 15°	- 50
7.50	Summit of ridge falls N.15°W. Descend 48°	+300
39.00	Foot of hill	-600
40.00	Set basalt stone, 14 x 10 x 5 ins., 10 ins. in ground, for 1/4 Sec. Cor., marked 1/4 on N. face. Raised mound of stone, 1 1/2 ft. high x 3 1/2 ft. base over Cor., from which, A cottonwood, 6 ins. diam., brs. N.10°E., 20 lks. dist., marked 1/4 S., B.T. A cottonwood, 18 ins. diam., brs. S.25°W., 30 lks. dist., marked 1/4 S., B.T.	
41.50	Pearson Creek, 10 lks. wide, runs N. Ascend 40°, Bluff 50 ft. high.	
84.50	Summit of mountain falls N. Descend 35°	+1600
108.50	Canyon, N., 10 ch.s down, turns N.E. Ascend 40°	- 950
125.50	Summit of ridge falls N. Descend 32°	+ 600
136.50	Intersect W. Bdy. of Tp., 516 lks. S. of Cor. to Secs. 13, 18, 19 & 24, which is a basalt stone, 22 x 12 x 10 ins., loose, in mound of stone, 1 1/2 ft. high x 3 ft. base, marked 3 notches on one edge. At point of intersection, I Set basalt stone, 14 x 10 x 8 ins., 10 ins. in ground, for Closing Cor. to Secs. 18 & 19, marked 3 notches on N., 3 notches on S. face & C.C. on E. Raised mound of stone 1 1/2 ft. high x 3 1/2 ft. base alongside. Pits impracticable. Var. 19°30' E. Land; mountainous, 136.50 chs. Soil; 5th rate. Timber; pine and cottonwood, undergrowth the same, 7.50 chs.	
	S. bet. Secs. 19 & 20. Descend 10° Var. 22°35'E.	
2.75	Ravine N.40°W. Ascend 34°	- 50
25.00	Summit of ridge falls N.30°W. Descend.	+300
40.00	Set basalt stone, 20 x 6 x 5 ins., 8 ins. in ground, for 1/4 Sec. Cor., marked 1/4 on W. face. Raised mound of stone,	