

Exteriors T.2 S., R.33 E., W. M.

Chains		Feet
40.00	Set basalt stone, 10 x 8 x 7 ins., 7 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A fir, 20 ins. diam., brs. N.25°E., 42 lks. dist., marked $\frac{1}{4}$ S., B.T. No other tree in limits; raised mound of stone alongside.	+990
52.25	Canyon, course S.W.	-600
68.50	Top of ridge, course S.W.	+1000
80.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for Cor. to Secs. 13, 18, 19 & 24, marked with 3 notches on N. & S. edges. Raised mound of stone alongside. Pits impracticable. Land; broken & mountainous. Soil; rocky 5th rate. Very little grass. Scattering pine timber in canyons.	
	N. bet. Secs. 13 & 18. Var. 22°30'E.	
21.17	Summit of divide bet. McKay and Birch Creeks, Wagon road, course N.W.	
33.00	Ravine, course E.	+1000
40.00	Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside. Pits impracticable.	-100
51.00	Canyon, course E.	-175
72.00	" " "	-350
80.00	Set basalt stone, 14 x 10 x 10 ins., 10 ins. in ground, for Cor. to Secs. 7, 12, 13 & 18, marked with 4 notches on S. and 2 notches on N. edges. Raised mound of stone alongside. Pits impracticable. Land; mountainous, 80 chs. Soil; 4th rate. Scattering pine, fir & tamarack timber in canyons.	
	N. bet. Secs. 7 & 12. Var. 19°E.	
3.00	Top of hill.	+600
34.25	Ravine, course N.E.	-100