

Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	E. on random line bet. Secs. 2 & 11. Var. 20°15'E.	
40.00	Set temp. 1/4 Sec. Cor.	
80.60	Intersect line, 18 lks. S. of Cor. to Secs. 1, 2, 11 & 12. Thence	
	S. 89°52' W. on true line.	
	Var. 21°45'E.	
18.35	Ravine, W.	-150
31.00	Canyon, N.W.	-350
36.20	Canyon, N.E.	-100
40.30	Set basalt stone, 18 x 12 x 8 ins., 12 ins. in ground, for 1/4 Sec. Cor., marked 1/4 on N. face, over which, I raised mound of stone, 18 ins. high with 3 1/2 ft. base.	
80.60	To Cor. to Secs. 2, 3, 10 & 11. Land; rolling, 40.30 chs. and mountainous, 40.30 chs. Scattering pine timber. Good grass. Soil; 1st & 2nd rate.	
	S. on true line bet. Secs. 10 & 11.	
	Var. 20°15'E.	
10.75	Gulch, W.	- 75
35.00	Summit	+150
40.00	Set basalt stone, 10 x 10 x 10 ins., 6 ins. in ground, for 1/4 Sec. Cor., marked 1/4 on W. face, around which, I raised mound of stone, 18 ins. high with 3 1/2 ft. base.	
47.25	Ravine, W.	- 50
55.40	Canyon, N.W.	-100
80.00	Set basalt stone, 14 x 10 x 8 ins., 9 ins. in ground, for Cor. to Secs. 10, 11, 14 & 15, marked with 4 notches on S. and 2 on E. edges; over which I raised mound of stone, 2 ft. high with 4 1/2 ft. base. Land; rough & mountainous, 80 chs. Soil; 3rd rate.	
	E. on random bet. Secs. 11 & 14.	
	Var. 20 °E.	
40.00	Set temp. 1/4 Sec. Cor.	
80.20	Intersect E. Bdy. line, 12 lks. S. of Cor. to Secs. 11, 12, 13 & 14. Thence	