

Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	<p>Secs. 4, 5, 8 &amp; 9, marked with 4 notches on E. and 5 on S. edges, over which, I raised mound of stone, 2 ft. high with <math>4\frac{1}{2}</math> ft. base.</p> <p>Land; mountainous &amp; rocky, 69.80 chs.</p> <p>Soil; 4th rate.</p>	
	<p>E. on random line bet. Secs. 4 &amp; 9.</p> <p style="text-align: right;">Var. <math>18^{\circ}45'E</math>.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect E. line at Cor. to Secs. 3, 4, 9 & 10.	
	Thence	
	W. on true line.	
13.10	Canyon, course N.	-100
13.90	" " "	- 20
36.54	Summit of ridge	+150
40.00	Set stone, 18 x 12 x 8 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, over which, I raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.	
74.19	Intersect U.R.Bdy., 4.04 chs., $S.30^{\circ}E$ . of $\frac{1}{2}$ mile Cor. in 76th mile and	
	Set basalt stone, 20 x 10 x 5 ins., 14 ins in ground, for U.R. Closing Cor., marked U.R. CC. on E. face, over which, I raised mound of stone, 2 ft. high with $4\frac{1}{2}$ ft. base.	
	Land; rolling. Soil; 3rd rate.	
	From Cor. to Secs. 5, 6, 31 & 32 on N. Bdy. of Tp., I run S. on true line bet. Secs. 5 & 6.	
	Var. $20^{\circ}E$ .	
	Ascend.	
9.80	Intersect U.R.Bdy., 4.08 chs., $N.43^{\circ}30'E$ . of 78th mile Cor. Set basalt stone, 10 x 12 x 16 ins., 8 ins. in ground, for U.R. Closing Cor., marked U.R. C.C. on S. face, over which I raised mound of stone, 2 ft. high with $4\frac{1}{2}$ ft. base.	
17.50	Daly Wagon road, course N.E.	