

Exteriors, T.2 S.,R.35 E.,W.M.

Chains		Feet
	<p>A tamarack, 15 ins. diam., brs. N.4°E., 58 lks. dist., marked T.2 S.,R.35 E.,S.19,B.T.</p> <p>No other tree in these limits.</p> <p>The first half mile is mountain table land.</p> <p>Soil; gravelly 2nd rate.</p> <p>Timber; pine, fir and tamarack.</p> <p>The last half mile diagonally down over precipices, 3000 ft.</p> <p>Soil, rocky in the extreme. Timber; none.</p>	
	N. bet. Secs. 19 & 24.	
	Var. 19°40'E.	
5.00	Brook, course N.W. Ascend over rugged, rocky mountain side.	
36.54	Summit of bluff, 3000 ft. above bottom of canyon, course NW.	
40.00	Set post, 3 ft. long, 3 ins. sq., 18 ins. in ground, on table land, in open timber, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on E. & W. faces, from which,	
	<p>A pine, 18 ins. diam., brs. N.73°E., 83 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A pine, 12 ins. diam., brs. N.81°W., 165 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>	
	Var. 19°E.	
	Descend through heavy timber with underbrush of willow & fallen timber.	
80.00	Lava stone, 36 x 60 x 12 ins., above ground, marked with 3 notches on N. & S. edges, on a bluff, on the S. side of canyon, in open timber, Cor. to Secs. 13, 18, 19 & 24, from which,	
	<p>A tamarack, 6 ins. diam., brs. N.85°E., 13 lks. dist., marked T.2 S.,R.35 E.,S.18,B.T.</p> <p>A tamarack, 6 ins. diam., brs. N.35°W., 25 lks. dist., marked T.2 S.,R.34 E.,S.13, B.T.</p> <p>A tamarack, 7 ins. diam., brs. S.66 ° W., 16 lks. dist., marked T.2 S.,R.34 E.,S.24,B.T.</p> <p>A tamarack, 7 ins. diam., brs. S.39°E., 33 lks. dist., marked T.2 S.,R.35 E.,S.19,B.T.</p>	
	Last half mile, mountain table land. Soil; gravelly 3rd rate. Timber; fir.	