

Subdivisional Lines, T.2 S., R.34 E., W. M.

| Chains | | Feet |
|--------|--|------------|
| 72.40 | Canyon, E. | -200 |
| 80.00 | Set stone, 16 x 18 x 18 ins., 12 ins. in ground, for Cor. to Secs. 5, 6, 7 & 8, marked with 5 notches on S. & E. edges, over which, I raised mound of stone, 2 ft. high with 4½ ft. base. Land; broken and mountainous, 80 chs. Soil; 4th rate. Some bunch grass. | |
| | E. on random line bet. Secs. 5 & 8. | |
| | Var. 18°30'E. | |
| 40.00 | Set temp. ¼ Sec. Cor. | |
| 79.30 | Intersect N. & S. line at Cor. to Secs. 4, 5, 8 & 9. | |
| | Thence | |
| | W. on true line. | Var. 20°E. |
| 21.00 | Gulch, N. | -100 |
| 36.00 | Canyon, N.E. | -400 |
| 39.65 | Set stone, 12 x 14 x 18 ins., 12 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face, over which, I raised mound of stone, 18 ins. high with 3½ ft. base. | |
| 56.00 | Gulch, S. | - 20 |
| 79.30 | To Cor. to Secs. 5, 6, 7 & 8. Land; mountainous and rough, 79.30 chs. Some bunch grass. Soil; poor, 4th rate. | |
| | W. on true line bet. Secs. 6 & 7. | |
| | Var. 18°30'E. | |
| 40.00 | Set stone, 10 x 12 x 14 ins., 10 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face, from which, A pine, 36 ins. diam., brs. N.75°E., 61 lks. dist., marked ¼ S., B.T. A pine, 6 ins. diam., brs. S.50°W., 75 lks. dist., marked ¼ S., B.T. Raised mound of stone, 18 ins. high with 3½ ft. base alongside. | |