

Portion East Bdy. Resurvey, T. 2 S., R. 34 E., W.M.

Chains		Feet
	<p>marked S.18 (lower blaze healed over, not opened) (Old B.T.). I additionally mark T.2 S., R.35 E.</p> <p>A tamarack stump, 10 ins. diam., brs. S.41°E., 33 lks. dist., marked T.2 S., R.35 E., S.19, B.T. (Old B.T.)</p> <p>A tamarack, 16 ins. diam., brs. S.61°15'W., 16 lks. dist., marks not legible; remarked T.2 S., R.34 E., S.24, B.T. (Old B.T.)</p> <p>A fir, 10 ins. diam., brs. N.37°45'W., 33 lks. dist., marked illegible (Old B.T.)</p> <p>A tamarack, 15 ins. diam., brs. N.15°W., 29 lks. dist., marked T.2 S., R.34 E., S.13, B.T. (New B.T.)</p> <p>A pine, 14 ins. diam., brs. S.62°45'E., 65 lks. dist., marked T.2 S., R.35 E., S.19, B.T. (New B.T.)</p>	
	<p>Thence N.0°11'E., resurveying line bet. Secs. 13 & 18. Descend 200 ft. to</p>	
8.04	Dry gulch, course W., ascend steep S. slope, 200 ft. to	
13.43	Top of ascent, brs. E. & W.; thence over rolling land.	
17.08	Intersect the E. Bdy. of U. I. R., 3.12 chs., S.19°31'W. from the 59½ Mile Cor.	
	<p>At the point of intersection Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for Closing Cor. of Secs. 13 & 18, with brass cap, marked</p>	
	<div style="text-align: center;"> </div>	
	<p>from which,</p> <p>A fir, 22 ins. diam., brs. S.59°15'E., 77 lks. dist., marked C.C., T.2 S., R.35 E., S.18, B.T.</p> <p>A fir, 16 ins. diam., brs. S.48°30'W., 64 lks. dist., marked C.C., T.2 S., R.34 E., S.13, B.T.</p>	
40.23	Intersect point for ½ Sec. Cor., located by reference to the old bearing trees. At the exact point, Set an iron post, 3 ft. long, 1 ins. diam., 26 ins. in the	