

Re-survey Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains	Feet
<p>From the Cor. of Secs. 23, 24, 25 & 26, N.89°46'W., retracing bet. Secs. 23 & 26; at 40.20 chs. find no trace of $\frac{1}{4}$ Sec. Cor.; set temp. Cor., and at 79.62 chs. fall 44 lks. N. of Cor. of Secs. 22, 23, 26 & 27, which is old post, marked S.23 on N.E., S.27 on S.E., S.26, T.2 S. on S.W. and S.22, R.34 E. on N.W. faces, with 2 notches on S. & E. edges. At the exact Cor. point</p>	S.W.
<p>Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground, for Cor. of Secs. 22, 23, 26 & 27, with brass cap, marked</p>	
<p>T2S R34E S22 S23 S27 S26 1917</p>	
<p>from which,</p>	
<p>A lodgepole pine, 12 ins. diam., brs. N.17°30' E., 36$\frac{1}{2}$ lks. dist., marked S.23, T.2 S., B.T. I remark it T.2 S., R.34 E., S.23, B.T. (Old B.T.)</p>	
<p>A fir, 30 ins. diam., brs. S.29°E., 32 lks. dist., marked in bark, S.27, B.T. I remark it in the wood, T.2 S., R.34 E., S.26, B.T. (Old B.T.)</p>	
<p>A lodgepole pine, 10 ins. diam., brs. S.64°W., 87 lks. dist., marks healed over. I remark it, T.2 S., R.34 E., S.27, B.T. (Old B.T.)</p>	
<p>A lodgepole pine, 12 ins. diam., brs. N.60°30'W., 23$\frac{1}{2}$ lks. dist., marked S.22, B.T. I remark it T.2 S., R.34 E., S.22, B.T. (Old B.T.)</p>	
<p>The point which agrees with the four bearing trees, as given in the original field notes, brs. N.9°W., 99 lks. dist. Evidently the deputy first placed the Cor. in that position and later moved it to its present location and marked new bearing trees, as above described, but in his returns, he described the wrong set of trees. The marks on two of these trees had been defaced. I deface the marks from the other two trees. To test this Cor., I retrace</p>	
<p>S., bet Secs. 26 & 27, and at 40.27 chs., intersect the $\frac{1}{4}$ Sec. Cor., which is a lodgepole pine, 4 ins. diam., marked and witnessed as described by the surveyor general; around the Cor. tree, which is dead, I raise a mound of stone, 4 ft. base, 2 ft. high.</p>	
<p>Returning to Cor. of Secs. 22, 23, 26 & 27; thence N.89° 55'E., resurveying the line bet. Secs. 23 & 26. Over rolling bench land, through medium heavy timber and undergrowth.</p>	
17.50	Descend 100 ft. to