

Re-survey Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
	N.0°01'W., on random line, bet. Secs. 2 & 3.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
51.25	Intersect N. Bdy. of Tp., 31 lks. E. of Cor. of Secs. 2 & 3.	
	Thence	
	S.0°14'E., on true line, bet. Secs. 2 & 3.	
	Over mountainous land, descending on S. & S.W. slopes,	
	250 ft. to	
28.60	"Elder Spring", brs. W., 110 lks. dist., flows W.	
	Enter dense undergrowth, brs. E. & W., ascend 150 ft. to	
38.00	Leave dense undergrowth, brs. E. & W.	
38.50	Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground,	
	for $\frac{1}{4}$ Cor. of Sec. 3 only, with brass cap, marked	
	$\frac{1}{4}$ S3 1917	
	from which,	
	A pine, 6 ins. diam., brs. N.83°30'W., 99 lks. dist.,	
	marked $\frac{1}{4}$ S.3, B.T.	
39.50	Top of spur, slopes W., descend S.W. slope, 15 ft. to	
41.25	Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground,	
	for $\frac{1}{4}$ Cor. of Sec. 2 only, with brass cap, marked,	
	$\frac{1}{4}$ S2 1917	
	from which,	
	A cross (X) on basalt stone, 5 x 4 x 3 ft., above	
	ground, brs. N.76°45'E., 80 lks. dist., marked $\frac{1}{4}$	
	S.2, B.O., beside the cross.	
	Descend 333 ft. to	
52.50	Dry gulch, course W., continue along broken W. slope.	
77.70	Dry gulch, course N.W., ascend 70 ft. to	
81.25	The Cor. of Secs. 2, 3, 10 & 11.	
	Land; mountainous.	
	Soil; rocky with scant loam, 3rd rate.	
	Timber; pine & fir, on N. slopes only.	
	Undergrowth; fir, pine, willow & ninebark, on N. slopes	
	only.	