

Re-survey Subdivisional Lines, T.2 S., R.34 E., W. M.

Chd ns		Feet
.75	Top of spur, slopes W.; descend 210 ft. to	
5.35	Bottom of dry ravine, course W.; ascend 530 ft. to	
20.87	Top of ascent, bench land, brs. N.60°W. & S.60°E.	
37.60	M.W. Mathis' spring brs. E., 60 lks. dist., course S.W.	
40.00	Set iron post, 3 ft. long, 1 in. diam., 12 ins. in ground,	
	surrounded by mound of stone, 4 ft. base, 1½ ft. high,	
	for ¼ Secs. Cor., with brass cap, marked,	
	$\frac{1}{4}$	
	$\begin{array}{c c} S14 & S13 \\ \hline 1917 & \end{array}$	
	1917	
	from which,	
	A pine, 22 ins. diam., brs. S.34°E., 68 lks. dist.,	
	marked ¼ S.13, B.T.	
	A pine, 22 ins. diam., brs. S.44°45'W., 23 lks. dist.,	
	marked ¼ S.14, B.T.	
80.00	Set iron post, 3 ft. long, 2 ins. diam., 8 ins. in ground,	
	to bedrock, surrounded by mound of stone, 5 ft. base,	
	2 ft. high, for Cor. to Secs. 11, 12, 13 & 14, with	
	brass cap, marked,	
	$\begin{array}{c} T2S R34E \\ S11 S12 \\ S14 S13 \\ \hline 1917 \end{array}$	
	1917	
	from which,	
	A pine, 36 ins. diam., brs. N.9°30'E., 338 lks. dist.,	
	marked T.2 S., R.34 E., S.12, B.T.	
	A pine, 36 ins. diam., brs. S.61°45'E., 349 lks. dist.,	
	marked T.2 S., R.34 E., S.13, B.T.	
	No other trees near.	
	Land; rolling, bench & mountainous.	
	Soil; light loam, shallow, on basalt bedrock.	
	Timber; pine & fir.	
	Undergrowth; none.	
	S.89°40'W., on random line, bet. Secs. 11 & 14.	
40.00	Set temp. ¼ Sec. Cor.	
79.94	Intersect N. & S. line, 7 lks. S. of Cor. of Secs. 10, 11,	
	14 & 15. Thence,	