

Re-survey Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
	N.0°14'W., on random line, bet. Secs. 1 & 2.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor..	
80.54	Intersect N. Bdy. of Tp., 11 lks. E. of Cor. of Secs. 1 & 2.	
	Thence	
	S.0°19'E., on true line, bet. Secs. 1 & 2.	
	Over mountainous land.	
	Descend broken S.W. slope, 320 ft. to	
16.12	Dry gulch, course W., ascend 180 ft. to	
24.13	Top of spur, slopes W.; descend 350 ft. to dry gulch.	
39.00	Enter timber & undergrowth, brs. E. & W.	
40.00	Dry gulch, course W.	
40.54	Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked,	
	$\frac{1}{4}$ S2 S1 1917	
	from which,	
	A pine, 16 ins. diam., brs. N.50°E., 45 lks. dist., marked $\frac{1}{4}$ S.1, B.T.	
	A fir, 8 ins. diam., brs. S.6°W., 25 lks. dist., marked $\frac{1}{4}$ S.2, B.T.	
	Ascend N. slope, 540 ft. to	
58.00	Top of spur, slopes W.	
	Leave brush & timber, brs. E. & W.; descend 160 ft. to	
74.25	Dry gulch, course W.; ascend 150 ft. to	
80.54	The Cor. of Secs. 1, 2, 11 & 12.	
	Land; mountainous.	
	Soil; shallow, on basalt bedrock, 3rd rate.	
	Timber; pine & fir.	
	Undergrowth; fir, serviceberry, ninebark & arrowood.	
	Good grass.	
General Description.		
<p>The land included in this survey lies near the summit of the Blue Mts., & consists of bench or table lands, cut by deep ravines. The bench lands are gently rolling and generally covered with timber.</p>		