

## Retracement Portion E. Bdy., T.2 S., R.34 E., W. M.

Chains		Feet
	<p>The true course &amp; dist. of this line from <math>\frac{1}{4}</math> Sec. Cor. is S., 40.23 chs.</p> <p>Land; rolling bench.</p> <p>Soil; light shallow loam on basalt rock, 3rd rate.</p> <p>Timber; fir, pine &amp; balsam.</p> <p>Undergrowth; balsam, fir &amp; willow.</p>	
	Retracement Subdivisional Lines, T.2 S., R.34 E., W. M.	
	<p>From the Cor. of Secs. 25, 30, 31 &amp; 36 on the E. Bdy. of Tp. W., bet. Secs. 25 &amp; 36.</p> <p>Over high rolling land, through heavy timber &amp; medium undergrowth.</p>	
36.00	Enter open glade, brs. N. & S.	
40.00	<p>Set iron post, 3 ft. long, 1 in. diam., 12 ins. in ground &amp; and 14 ins. in mound of stone, for <math>\frac{1}{4}</math> Sec. Cor., with brass cap, marked,</p> <p style="text-align: center;"><math>\frac{1}{4}</math> S25 <math>\frac{1}{4}</math> S36 1917</p> <p>from which,</p> <p style="padding-left: 40px;">A pine, 16 ins. diam., brs. S.6°45'W., 400 lks. dist., marked <math>\frac{1}{4}</math> B.36, B.T.</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., brs. N.38°45'E., 459 lks. dist., marked <math>\frac{1}{4}</math> S.25, B.T.</p>	
49.00	Leave bench land, brs. N.W. & S.E.; descend 320 ft. to	
63.09	<p>Intersect E. Bdy. of original Umatilla Indian Reservation, N.20°20'E., 7.46 chs. from the 62 Mile Cor.</p> <p>At the point of intersection</p> <p>Set iron post, 3 ft. long, 2 ind. diam., 24 ins. in ground, for Closing Cor. of Secs. 25 &amp; 36, with brass cap, marked,</p> <p style="text-align: center;">T2S R34E <del>S25</del> <del>S36</del> C.C. 1917</p>	
	<p>from which,</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., brs. N.54°E., 246 lks. dist., marked C.C., T.2 S., R.34 E., S.25, B.T.</p> <p style="padding-left: 40px;">A fir, 24 ins. diam., brs. S.60°E., 29 lks. dist.,</p>	