

Retracement Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains		Feet
	<p>marked C.C., T.2 S., R.34 E., S.36, B.T.</p> <p>The Closing Cor. of that portion of Secs. 25 & 36 within the original Umatill Indian Reservation, brs. S.20°20'W., 140 lks. dist.</p> <p>Land; rolling bench & mountainous.</p> <p>Soil; light scant loam, 3rd rate.</p> <p>Timber; pine & fir.</p> <p>Undergrowth; balsam, pine & willow.</p>	
14.20	<p>From Cor. of Secs. 19, 24, 25 & 30, on E. Bdy. of Tp. W. bet. Secs. 24 & 25</p> <p>Ascend N.E. slope, through heavy timber & medium undergrowth, 560 ft. to</p> <p>Top of ascent; over rolling bench land, brs. N.W. & S.E.</p>	
34.36	<p>Intersect E. Bdy. of original Umatill Indian Reservation, N.19°14'E., 13.05 chs. from the 61 Mile Cor.</p> <p>At the point of intersection</p> <p>Set iron post, 3 ft. long, 2 ins. diam., 14 ins. in ground and 10 ins. in mound of stone, for Closing Cor. of Secs. 24 & 25, with brass cap, marked,</p> <div style="text-align: center;"> <p>T2S R34E S24 S25 CC 1917</p> </div> <p>from which,</p> <p>A pine, 28 ins. diam., brs. N.70°E., 59 lks. dist., marked C.C., T.2 S., R.34 E., S.24, B.T.</p> <p>A pine, 8 ins. diam., brs. S.57°E., 48 lks. dist., marked C.C., T.2 S., R.34 E., S.25, B.T.</p> <p>The Closing Cor. of that portion of Secs. 24 & 25 within the original Umatilla Indian Reservation, brs. S.19°14'E., 16 lks. dist.</p> <p>Land; mountainous & rolling bench.</p> <p>Soil; light shallow loam, 2nd rate.</p> <p>Timber; pine & fir.</p> <p>Undergrowth; arrowwood, willow, pine & fir.</p>	
	<p>From the Cor. of Secs. 13, 18, 19 & 24, on E. Bdy. of Tp.</p>	