

## Retracement Portion Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains Feet

N., bet. Secs. 31 &amp; 32.

Over high rolling land, through heavy timber &amp; medium undergrowth.

32.67 Intersect S.Bdy. of original Umatilla Indian Reservation, N.89°55'W., 4.32 chs. from the 66 $\frac{1}{2}$  Mile Cor.

The soil at the point of intersection is so shallow that it is impracticable to set an iron post; therefore, at point, 25 lks. S. of true Cor.

Set iron post, .3 ft. long, 2 ins. diam., 12 ins. in ground and 12 ins. in mound of stone, for witness Cor. to Closing Cor. of Secs. 31 &amp; 32, with brass cap, marked,

W C  
T2S R34E  
UIR.  
S31|S32  
C C.  
1917

From point for true Closing Cor. of Secs. 31 &amp; 32;

A fir, 8 ins. diam., brs. S.45°30'E., 51 lks. dist., marked C.C., T.2 S., R.34 E., S.32, B.T.

A fir, 24 ins. diam., brs. S.25°45'W., 119 lks. dist., marked C.C., T.2 S., R.34 E., S.31, B.T.

The Closing Cor. of that portion of Secs. 31 &amp; 32, within the original Umatilla Indian Reservation, brs. N.89°55'W., 182 lks. dist.

Land; high rolling bench.

Soil; light shallow loam, 3rd rate.

Timber; yellow pine, lodgepole pine, balsam &amp; fir.

Undergrowth; willow, balsam &amp; lodgepole pine.

This portion of the Tp. lies on summit of Blue Mts. The soil is light volcanic ash, very shallow over basalt rock and is good for grazing.

It is nearly all timbered with scattering yellow pine, fir, tamarack and balsam, not of commercial value. The land is principally valuable for grazing. There are no settlers.

Oct. 18, 1917.

L.E. Wilkes  
U.S. Surveyor.