

Subdivisional Lines, T.2 S., R.35 E., W.M.
 As surveyed by Rufus S. Moore, U.S. Deputy Surveyor,
 Under Contract No. 451, Dated June 12, 1882.

Chains		Feet

	From the Cor. to Secs. 3, 4, 33 & 34 on S. Bdy. of Tp.	
	N. bet. Secs. 33 & 34	

80.00	Set a post, 4 ft. long, 4 ins. sq., 24 ins. in ground, on W. slope of hill, for Cor. to Secs. 27, 28, 33 & 34, marked,	
	T.2 S., R.35 E., S.27, on N.E.	
	T.2 S., R.35 E., S.28 on N.W.	
	S.33 on S.W. and	
	S.34 on S.E. faces, with	
	1 notch on S. and	
	3 notches on E. edges, from which,	
	A pine, 4 ins. diam., brs. N.55°E., 16 lks. dist., marked T.2 S., R.35 E., S.27, B.T.	
	A pine, 5 ins. diam., brs. N.63°W., 31 lks. dist., marked T.2 S., R.35 E., S.28, B.T.	
	A fir, 4 ins. diam., brs. S.79°W., 44 lks. dist., marked T.2 S., R.35 E., S.33, B.T.	
	A pine, 16 ins. diam., brs. S.55°E., 15 lks. dist., marked T.2 S., R.35 E., S.34, B.T.	
	Land; high & mountainous, general slope to W.	
	Soil; 2nd rate.	
	Heavily timbered with pine, fir & tamarack and	
	Dense undergrowth of pine, fir & tamarack.	

	N. bet. Secs. 27 & 28.	
	Var. 16°30'E.	
	Alongside of hill, slopes W.	
21.00	Dry gulch, course W., 100 ft. above Sec. Cor.	
23.42	Dry gulch, course S.W.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, in last noted dry gulch, course S.20°E., marked $\frac{1}{4}$ S. on W.	