

Subdivisional Lines, T.2 S., R.35 E., W M.

Chains		Feet
72.20	Dry gulch, course N.	
72.50	Leave meadow, brs. N. & S.	
79.70	Intersect N. & S. line, 63 lks. S. of Cor. to Secs. 21, 22, 27 & 28, Thence I run S.89°33'W., on true line bet. Secs. 21 & 28.	
39.85	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 9 ins. diam., brs. N.71°W., 10 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 10 ins. diam., brs. S.66°W., 23 lks. dist., marked $\frac{1}{4}$ S., B.T.	
79.70	The Cor. to Secs. 20, 21, 28 & 29. Land; high & mountainous. Soil; 2nd rate. Heavily timbered with pine, fir and tamarack, 71.50 chs. Dense undergrowth of pine, fir, tamarack & mountain laurel.	
N. bet. Secs. 20 & 21. Var. 19°E.		
9.50	Dry gulch, course W., 25 ft. below Sec. Cor.	
11.70	Indian Trail, brs. N.W. & S.E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A fir, 6 ins. diam., brs. N.23°E., 25 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 6 ins. diam., brs. S.54°W., 10 lks. dist., marked $\frac{1}{4}$ S., B.T.	
77.00	Enter glade, brs. E. & W.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 16, 17, 20 & 21, 150 ft. above $\frac{1}{4}$ Sec. Cor., marked, T.2 S., R.35 E., S.16, on N.E. T.2 S., R.35 E., S.17, on N.W. S.20 on S.W. and S.21 on S.E. faces; with	