

## Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet
50.00	Enter prairie, brs. E. & W.	
55.00	Leave " " " "	
64.00	Descend hill, brs. " " "	
72.00	Dry ravine, course W., 400 ft. below top of hill, & ascend.	
72.50	Leave timber, brs. E. & W.	
77.25	Top of hill, brs. E. & W., 400 ft. above ravine & enter timber, brs. E. & W.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 19, 20, 29 & 30, marked, T.2 S., R.35 E., S.20 on N.E. T.2 S., R.35 E., S.19 on N.W. S.30 on S.W. and S.29 on S.E. faces, with 2 notches on S. and 5 notches on E. edges, from which, A pine, 22 ins. diam., brs. N.62°E., 18 lks. dist., marked T.2 S., R.35 E., S.20, B.T. A pine, 24 ins. diam., brs. N.76°W., 176 lks. dist., marked T.2 S., R.35 E., S.19, B.T. A pine, 20 ins. diam., brs. S.23°W., 116 lks. dist., marked T.2 S., R.35 E., S.30, B.T. A pine, 12 ins. diam., brs. S.19°E., 105 lks. dist., marked T.2 S., R.35 E., S.29, B.T. Land; high & mountainous. Soil; 2nd & 3rd rate. Heavily timbered with pine, fir & tamarack, 63.25 chs. and Some dense undergrowth of pine, fir and tamarack. <hr/> E. on random line bet. Secs. 20 & 29. Var. 19°E. 7.00 Descend hill, brs. N.E. & S.W. 77.50 Enter glade, brs. " " " 20.00 Leave glade & enter timber, brs. N. & S. 25.50 Dry ravine, course S.65°W., 250 ft. below top of hill, and descend. 40.00 Set temp. $\frac{1}{4}$ Sec. Cor., 200 ft. above ravine.	