

Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet Feet
	and mound of stone alongside. Thence I run E. on true line bet. Secs. 19 & 30. Var. 19°40'E.	
39.74	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A fir, 20 ins. diam., brs. N.27°W., 34 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 15 ins. diam., brs. S.55°E., 48 lks. dist., marked $\frac{1}{4}$ S., B.T.	
79.74	The Cor. to Secs. 19, 20, 29 & 30. Land; high & mountainous. Soil; 2nd & 3rd rate. Timber: pine, fir & tamarack, and Some undergrowth of pine, fir & tamarack.	
	NY bet. Secs. 19 & 20. Var. 19°E.	
30.30	Enter prairie, brs. E. & W.	
34.00	Top of ridge, brs. " " ", 75 ft. above last Sec. Cor.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 16 ins. diam., brs. N.85°E., 12 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 9 ins. diam., brs. N.66°W., 161 lks. dist., marked $\frac{1}{4}$ S., B.T.	
43.30	Leave prairie & enter timber; brs. E. & W. & descend.	
44.50	Enter glade, brs. E. & W.	
48.50	Leave glade & enter timber, brs. E. & W.	
60.00	Dry ravine, course N.30°W., 400 ft. below $\frac{1}{4}$ Sec. Cor.	
67.40	Indian Trail, brs. E. & W., 200 ft. above ravine.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 17, 18, 19 & 20, 50 ft. above Indian Trail, marked, T.2 S., R.35 E., S.17, on N.E. T.2 S., R.35 E., S.18 on N.W.	