

## Subdivisional Lines, T.2 S., R.35 E., W. M.

| Chains |  | Feet |
|--------|--|------|
|        | Heavily timbered with spruce, fir, pine & tamarack & Dense undergrowth of spruce, fir, pine, tamarack and some mountain laurel & yew, 79.40 chs.   |      |
|        | W. on random line bet. Secs. 18 & 19.<br>Var. 23°30'E.   |      |
|        | Gradual descent.   |      |
| 31.72  | Indian Trail, brs. N.W. & S.E.   |      |
| 38.90  | Dry bed of creek in ravine, course N.W., 10 lks. wide, 400 ft. below Sec. Cor. and ascend.   |      |
| 40.00  | Set temp. $\frac{1}{4}$ Sec. Cor., 50 ft. above ravine.  |      |
| 79.76  | Intersect W. Bdy. of Tp., 62 lks. N. of Cor. to Secs. 13, 24, 18 & 19, 400 ft. above $\frac{1}{4}$ Sec. Cor., which is a lava stone, 60 x 36 x 12 ins., above ground, marked with 3 notches on N. & S. edges, from which,<br>A tamarack, 6 ins. diam., brs. N.85°E., 13 lks. dist., marked T.2 S., R.35 E., S.18, B.T.<br>A tamarack, 6 ins. diam., brs. N.35°W., 24 lks. dist., marked T.2 S., R.34 E., S.13, B.T.<br>A tamarack, 7 ins. diam., brs., S.39°E., 33 lks. dist., marked T.2 S., R.35 E., S.19, B.T.<br>A tamarack, 7 ins. diam., brs. S.66°W., 16 lks. dist., marked T.2 S., R.34 E., S.24, B.T. |      |
|        | Thence I run<br>N.89°33'E. on true line bet. Secs. 18 & 19.  |      |
| 39.76  | Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which,<br>A pine, 3 ins. diam., brs. N.46°W., 24 lks. dist., marked $\frac{1}{4}$ S., B.T.<br>A pine, 3 ins. diam., brs. S.7°E., 53 lks. dist., marked $\frac{1}{4}$ S., B.T.   |      |
| 79.76  | The Cor. to Secs. 17, 18, 19 & 20.<br>Land; high & mountainous.<br>Soil; 2nd & 3rd rate.<br>Heavily timbered with fir, spruce, tamarack & pine and Some dense undergrowth of fir, spruce, tamarack, pine, mountain laurel & willow.<br>Sept. 28, 1882.   |      |