

## Re-survey Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet
12.50	Top of ascent, brs. N. & S., descend 100 ft. to	
20.85	Dry gulch, course N.; ascend 70 ft. to	
28.00	Top of ascent, brs. N. & S.	
40.00	Set an iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked,	
	$\begin{array}{r} S6 \\ \frac{1}{4} S7 \\ \hline 1917 \end{array}$	
	from which,	
	A yellow pine, 16 ins. diam., brs. S.4°30'E., 38 lks. dist., marked $\frac{1}{4}$ S.7, B.T.	
	A yellow pine, 16 ins. diam., brs. N.55°W., 45 lks. dist., marked $\frac{1}{4}$ S.6, B.T.	
48.77	Intersect E.Bdy. of Original Umatilla Indian Reservation, 11.85 chs., S.17°26'W. from 57 $\frac{1}{2}$ Mile Cor.	
	At the point of intersection	
	Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground for Closing Cor. of Secs. 6 & 7, with brass cap, marked	
	$\begin{array}{r} T2S R35E \\ CC- S6 \\ S7 \\ \hline 1917 \end{array}$	
	from which,	
	A yellow pine, 18 ins. diam., brs. S.76°15'W., 157 lks. dist., marked C.C., T.2 S., R.35 E., S.7, B.T.	
	A yellow pine, 24 ins. diam., brs. N.50°W., 126 lks. dist., marked C.C., T.2 S., R.35 E., S.6, B.T.	
	Land; rolling & bench	
	Soil; light, shallow loam, on basalt bedrock, 2nd rate.	
	Timber; yellow pine.	
	Undergrowth; yellow pine & balsam.	
	<u>General Description.</u>	
	The land in this Tp. included in this survey lies near the summit of the Blue Mts. and consists of bench or table land cut by deep canyons. The bench land is generally rolling and covered with timber.	
	Soil is fine volcanic ash overlying basalt or lava, which is usually not more than two feet below the surface.	