

Retracement & Survey Portion Subdivisions, T. 2 S., R. 35 E., W.M.

Chains	Feet
	is N.89°29'W., 40.30 chs.
	From the $\frac{1}{4}$ Sec. Cor.
	W., surveying line bet. Secs. 7 & 18, continuing my measurements.
52.54	Intersect E. Bdy. of original Umatilla Indian Reservation, S.18°09'W., 9.15 chs. from the 58 $\frac{1}{2}$ Mile Cor.
	At the point of intersections
	Set an iron post, .3 ft. long, 2 ins. diam., 24 ins. in the ground, for Closing Cor. of Secs. 7 & 18, with brass cap marked
	<p>T2S R35E</p> <p>UJR $\frac{S7}{S18}$ CC</p> <p>1917</p>
	from which
	A fir, 8 ins. diam., brs. S.7°E., 23 lks. dist., marked C.C., T.2 S., R.35 E., S.18, B.T.
	A pine, 16 ins. diam., brs. N.89°E., 46 lks. dist., marked C.C., T.2 S., R.35 E., S.7, B.T.
	The Closing Cor. of that portion of Secs. 7 & 18, within the original Umatilla Indian Reservation, brs. S.18°09'W., 6.86 chs. dist.
	Land; rolling bench.
	Soil; shallow loam on basalt, 2nd rate.
	Timber; pine & fir.
	Undergrowth; willow, ninebark, pine & fir.
	<hr/>
	From the Cor. to Secs. 5, 6, 7 & 8
	N., retracing line bet. Secs. 5 & 6.
	Over rolling bench land, through heavy timber & dense undergrowth.
3.50	Descend N. slope, 175 ft. to
17.00	Foot of descent, brs. E. & W.; over rolling land descending gradually 50 ft. to
35.20	Dry run, course W.
40.09	Fall 20 lks. E. of $\frac{1}{4}$ Sec. Cor., which is old post, badly decayed, marked & witnessed as described by the Surveyor