

Exterior Bdys., T.3 N., R.27 E., W. M.
 As surveyed by Ebenezer E. Haft, U.S. Deputy Surveyor,
 Under Contract No. 91,
 Dated Sept. 11, 1860.

Chains		Feet
	<p>From the Cor. to Tps. 2 & 3 N., Rs. 26 & 27 E., I run E. on random line bet. Tps. 2 & 3 N., R.27 E.</p> <p>Set temp. $\frac{1}{2}$ mile & mile posts, on 40.00 & 80.00 chs. I find the Tp. line to be 6 miles, 5 chs. & 20 lks. & the falling to be 120 lks. S. of the Tp. Cor.</p> <p>The Correction for the true line will, therefore, be E. 520 lks. & 20 lks. N. per mile.</p> <p>From the Cor. to Tps. 2 & 3 N., Rs. 27 & 28 E., I run S. $89^{\circ}51'W$ on a true line bet. Secs. 1 & 36.</p> <p style="text-align: right;">Var. $19^{\circ}50'E$.</p>	
10.00	Enter Butter Creek bottom.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
50.00	Channel of Butter Creek (dry), 20 lks. wide, course N.	
80.00	Set post for Cor. to Secs. 1, 2, 35 & 36, in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
	Land; level.	
	Soil; on Butter Creek bottom, 1st rate.	
	Sept. 25, 1860.	
	<hr/>	
	S. $89^{\circ}51'W$., bet. Secs. 2 & 35.	
	Var. $19^{\circ}55'E$.	
6.25	Trail up Butter Creek, brs. S.-S.W.	
10.00	Leave Butter Creek valley & ascend table land.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
56.00	Road from the Dalles to Walla Walla, E.-N.E.	
80.00	Set post for Cor. to Secs. 2, 3, 34 & 35, in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
	Soil; 2nd & 3rd rate.	
	Land; hilly & rolling.	
	<hr/>	
	S. $89^{\circ}51'W$. bet. Secs. 34 & 3.	
	Var. $20^{\circ}E$.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits &	