

Subdivisional Lines, T.3 N., R.27 E., W. M.

Chains		Feet
	<p>E. on random line bet. Secs. 13 & 24.</p> <p style="text-align: right;">Var. 19°45'E.</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.85	Intersect E. Bdy. of Tp., 24 lks. S. of Cor. to Secs. 13, 24, 18 & 19, from which Cor., I run S.89°50'W. on true line bet. Secs. 13 & 24.	
39.92 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
79.85	The Cor. to Secs. 13, 14, 23 & 24. Soil; 3rd rate, producing grass. Land; rolling & hilly.	
N. bet. Secs. 13 & 14.		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 11, 12, 13 & 14, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; sand, 3rd rate, producing some grass. Land; rolling.	
E. on random line bet. Secs. 12 & 13.		
	Var. 19°55'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.19	Intersect E. Bdy. of Tp., 24 lks. S. of Cor. to Secs. 12, 13, 7 & 18, from which Cor., I run S.89°50'W. on true line bet. Secs. 12 & 13.	
40.09 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
80.19	The Cor. to Secs. 11, 12, 13 & 14. Soil; light, sandy, 3rd rate. Land; rolling, but little undergrowth or vegetation.	
N. bet. Secs. 11 & 12.		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	