

T. 3 N. R. 28 E.

Chains

From the established corner to Townships 3 and 4, North of Ranges 27 and 28 East, run East on a random line on the north boundaries of Sections 6, 5, 4, 3, 2 and 1.

Variation 20° 30' East.

Set temporary half mile and mile posts at every 40 and 80 chains, and at 5 miles, 76 chains, to a point 4.20 chains North of the corner to Townships 3 and 4 North of Ranges 28 and 29 East.

The correction will, therefore, be 4 chains West, and 70 links South per mile, and the true course of line N.89° 30' W.

N.89° 30' W. on true line between Secs. 1 & 36, T.3 N.R. 28 E.

- 16.50 Spring branch, 28 links wide, course North.
 40.00 Set post for $\frac{1}{4}$ Section corner in mound of earth, with charred stake, trenches, pits &c., as per instructions.
 44.50 Spring branch, 30 links wide, course North.
 70.00 Leave bottom. Course N.W. and S.E.
 80.00 Set post for corner to Sections 1 and 2, 35 and 36 in mound of earth with charred stake, trenches, pits &c., as per instructions.

Land, level.

Soil, 1st rate.

Oct. 11, 1859.

N.89° 30' W. on true line between Sections 2 and 35.

Variation 19° 45' East.

- 40.00 Set post for Qr. Section corner in mound of earth, established as per instructions.
 80.00 Set post for course to Sections 2 and 3, 34 and 35 in earth mound established as per instructions.

Land, level.

Soil, good 2nd rate.