

## T. 3, N. of R. 28 E.

Chains	
	N. 89° 30' W. on true line between Sections 3 and 34. Variation 20° 10' East.
40.00	Set post for $\frac{1}{4}$ Section corner in mound of earth established as per instructions.
80.00	Set post for corner to Sections 3 and 4, 33 and 34, in mound of earth established as per instructions. Land, rolling. Soil, 2nd rate, very sandy and mostly covered with cactus.
	N. 89° 30' W. on true line between Sections 4 and 33. Variation 20° 05' East.
40.00	Set post for $\frac{1}{4}$ Section corner in mound of earth, established as per instructions. From this corner, the mouth of Butter Creek bears N. 15° W; about $1\frac{1}{2}$ miles distant; also a noted point of rocks on the Columbia River, near the mouth of the Umatilla River, bears due North and is about 9 miles distant.
80.00	Set post for corner of Sections 4 and 5, 32 and 33, in mound of earth, established as per instructions. Land, gently rolling. Soil, 2nd rate and sandy and partially covered with cactus.
	N. 89° 30' W. on true line between Secs. 5 and 32. Variation 20° 15' East.
3.00	Enter bottoms of Butter Creek; course N. & S.
16.50	Butter Creek course N.E. 15 links wide.
40.00	Set post for corner to $\frac{1}{4}$ Section, in mound of earth established as per instructions.
79.00	Leave bottom, course N.E. and S.W.
80.00	Set post for Corner to Sections 5 and 6, 31 and 32, in mound of earth established as per instructions. Land, nearly level. Soil, 1st and 2nd rates.