

## T. 3 N. R. 28 E.

## Chains

N.89° 30' W. on true line between Sections 6 and 31.

Variation 20° 15' East.

40.00 Set post for  $\frac{1}{4}$  Section corner in mound of earth, established as per instructions.

76.00 Intersect the corner to Townships 3 & 4, North of Ranges 27 & 28 East.

Land, gently rolling.

Soil, 2nd rate and sandy.

October 12th, 1859.

---

General Description

This Township contains but little 1st rate land, its soil being chiefly composed of a very sandy loam, of too light a nature to admit of a profitable cultivation, and is entirely destitute of timber.

It is generally covered with bunch grass, and will, therefore, make reasonably good pasturage; but in this respect, it will not be greatly advantaged by the generous beds of cactus scattered over its surface.

---

Field Notes of the Survey of the  
Subdivision lines in Tp. 3 N. R. 28 E.  
Survey made by N. H. Gates, under  
Contract No. 84, dated July 22, 1859.

---

North between Secs. 35 & 36.

9.70 Trail bears N.E. & S.W.

40.00 Set post for  $\frac{1}{4}$  Sec. corner in mound of earth &c as per instructions.

80.00 Set post for corner to Secs. 25, 26, 35 & 36 in mound of earth &c., as per instructions.

Land, level.

Soil, 2nd rate.

---

East on random line between Secs. 25 & 36.

40.00 Set temp.  $\frac{1}{4}$  Sec. corner.

80.00 Intersect East boundary 70 links North of Sec. corner.