

Subdivisions T. 3, N. R. 28 E.

Chains	
	West on true line between Secs. 4 & 9.
39.78	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.56	The corner to Secs. 4, 5, 8 & 9. Land, gently rolling. Soil, 1st rate.
	North between Secs. 4 & 5 on random line. Variation 20° East.
40.00	Set post for temp. 1/4 Sec. corner.
80.50	Intersect North boundary 40 links East of Sec. corner. S.00° 17' E. on true line between Secs. 4 & 5.
40.50	A post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.50	The corner to Secs. 4, 5, 8 & 9. Land, level. Soil, 2nd rate, very sandy. Sept. 26th, 1859.
	North between Secs. 31 & 32.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 29, 30, 31 & 32 in mound of earth &c., as per instructions. Land, level. Soil, 1st rate.
	East on a random line between Secs. 29 & 32.
40.00	Set post for temp. 1/4 Sec. corner.
80.00	Intersect N & S line 30 links North of Sec. corner. N. 89° 47' W, on true line between Secs. 29 & 32.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	The corner to Secs. 29, 30, 31 & 32. Land level. Soil, 1st rate.