

## Subdivisions T. 3, N. R. 28 E.

Chains	
37.23	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
44.00	Enter bottom, bears N. & S.
77.23	The corner to Secs. 7, 8, 17 & 18. Land, level. Soil, 1st rate.
<hr/> North between Secs. 7 & 8. Variation $20\frac{1}{2}^{\circ}$ East.	
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 6, 7, 5 & 8 in mound of earth &c., as per instructions. Land, level. Soil, 1st rate.
<hr/> East on random line between Secs. 5 & 8.	
40.00	Set post for temp. 1/4 Sec. corner.
79.68	Intersect N & S Line 70 links North of corner. N. $89^{\circ} 30'$ West on true line between Secs. 5 & 8.
30.00	Enter Bottom bears N.E. & S.W.
35.00	Butter Creek 25 links runs N.W.
39.84	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.68	The corner to Secs. 5, 6, 7 & 8. Land, level. Soil, 1st rate.
<hr/> West on random line between Secs. 6 & 7.	
40.00	Set post for temp. 1/4 Sec. corner.
76.35	Intersect West boundary at Sec. corner. East on true line between Secs. 6 & 7.
36.35	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
64.35	Enter bottom N. $20^{\circ}$ E. & S. $10^{\circ}$ W.