

Chains

North between Sections 13 and 14.

Variation 20° East.

40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

43.50 Road bears E. & W.

80.00 Set post for corner to Secs. 11, 12, 13 and 14 in mound of earth &c., as per instructions.

Land, gently rolling.

Soil, good 2nd rate.

Sept. 16th, 1859.

East on random line between Secs. 12 & 13.

40.00 Set post for temp. 1/4 Sec. corner.

79.45 Intersect East boundary 50 links South of Section corner.
S. 89° 39' W. on true line between Secs. 12 and 13.

39.73 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

79.45 The corner to Secs. 11, 12, 13 and 14 in mound of earth.

Land, gently rolling.

Soil, 2nd rate.

North between Sections 11 and 12.

Variation 20° 10' East.

40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

80.00 Set post for corner to Secs. 1, 2, 11 & 12 in mound of earth &c., as per instructions.

Land, gently rolling.

Soil, 2nd rate.

East on random line between Secs. 1 and 12.

40.00 Set post for 1/4 Sec. corner.

79.45 Intersect East boundary 35 links South of Sec. corner.
S. 89° 45' W. on true line between Secs. 1 and 12.

39.73 Set post for 1/4 Sec. corner in mound of earth &c., as per