

Subdivisions, T. 3, N. R. 29 E.

Chains	<p>North between Sections 10 and 11.</p> <p style="text-align: right;">Variation 20° East.</p> <p>12.00 Trail bears N. W. and S. E.</p> <p>40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.</p> <p>80.00 Set post for corner to Secs. 2, 3, 10 and 11 in mound of earth &c., as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate.</p>
	<p>East on random line between Sections 2 and 11.</p> <p>40.00 Set post for temporary 1/4 Sec. corner.</p> <p>80.20 Intersect N. & S. line at the Section corner.</p> <p>West on true line between Sections 2 and 11.</p> <p>40.10 Set post for 1/4 Section corner in mound of earth &c., as per instructions.</p> <p>80.20 The corner to Secs. 2, 3, 10 and 11.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate.</p>
	<p>North on random line between Secs. 2 & 3.</p> <p style="text-align: right;">Variation 20° East.</p> <p>40.00 Set post for temporary 1/4 Sec. corner.</p> <p>80.50 Intersect North boundary 20 links East of corner.</p> <p>S.9' East on true line between Sections 2 and 3.</p> <p>40.50 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.</p> <p>80.50 The corner to Sections 2, 3, 10 & 11.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate.</p>
	<p>North between Sections 33 and 34.</p> <p>30.50 Indian trail bears N. W. and S. E.</p> <p>40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.</p>