

## Subdivisions, T. 3, N. R. 29 E.

Chains	
80.00	Set post for corner to Sections 27, 28, 33 & 34 in mound of earth &c., as per instructions. Land, gently rolling. Soil, good 2nd rate. Sept. 18th, 1859.
40.00	East on a random line between Sections 27 & 34. Set post for temporary 1/4 Section corner.
79.87	Intersect N. & S. line 35 links South of Sec. corner. S. 89° 45' W. on true line between Secs. 27 and 34.
10.60	Indian Trails from Umatilla River to Butter Creek bears N.W. and S.E.
39.94	Set post for 1/4 Section corner.
60.77	Trail in ravine bears N.W. and S.E.
79.87	The corner to Sections 27, 28, 33 and 34 in mound of earth &c., as per instructions. Land, gently rolling. Soil, good 2nd rate.
40.00	North between Sections 27 and 28. Variation 19°45' East.
40.00	Set post for 1/4 Section corner in mound of earth &c., as per instructions.
59.25	Bluff Rock, 200 ft. high, bears East and West.
60.00	Foot of same.
80.00	Set post for corner to Sections 21, 22, 27 and 28 in mound of earth &c., as per instructions. Land, hilly. Soil, 2nd rate.
40.00	East on random line between Sections 22 and 27. Set post for temporary 1/4 Section corner.
79.76	Intersect N. & S. line 70 links South of corner. S. 89° 30' West on true line between Secs. 22 and 27.
14.00	Enter Timber Bottom, bears North and South.